

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE**NAME OF WORK:- Development of Secondary Drains in Ward No.06**

Sl. No.	Quantity.	Description	Unit	Rates	
1	85.98	Earthwork in excavation for foundation of structure like culverts, retaining wall etc., as per drawing and technical specification, including setting out, construction of shoring and bracing, dressing of sides and bottom, back filling with approved material, disposal of balance earth as per specification, including cost of labour, HOM etc., complete. In all kinds of soil by manual means. (P.No.256, I.No.34.15.1 of PW,P&IWTD S.R 2018-19)	Cum	273.40	Rupees Two Hundred Seventy Three and Paise Forty Only
2	7.92	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications, MORTH specifications No. 408, (P.No.13, I.No.4-1.2 of PW,P&IWTD S.R 2018-19)	Cum	5505.64	Rupees Five Thousand Five Hundred Five and Paise Sixty Four Only
3	7.92	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centring shuttering cost of material HOM of machinery curing etc., complete excluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW, P&IWTD S.R 2018-19) wall & bottom thickness 15cm.	Cum	5770.64	Rupees Five Thousand Seven Hundred Seventy and Paise Sixty Only

4	85.20	KSRB 5-11 : Providing and constructing load bearing wall with having block density not less than 1800 kg/m ³ and having a minimum average compressive strength 5.00 N/mm ² confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials labour charegs, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 .-do- solid concrete blocks of size 400x150x200 mm (Page No.27. litem no.5.27.2 of KPWD S.R Bangalore Circle (2018-19)	Sqm	1010.18	Rupees One Thousand Ten and Paise Eighteen Only
5	8.52	KSRB 4-1.1: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No.4.1 of PW,P&IWTD S.R 2018-19)	Cum	5599.98	Rupees Five Thousand Five Hundred Ninety Nine and Paise Ninety Eight Only
6	85.20	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only

"OTS APPROVED"

Signature
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕಿ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Signature 01/12
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Signature 01/12